Statement of probable quantities for constructing Stall, Motor Shed and Cattle Sheds for Mr. Chamappaji Urs' Bungalow, Mysore.

No.	Quantity	Details of work	Per	Remarks
1	40	Earth work excavation	C. yd.	
2	205	Concrete with mortar	C. ft.	
3	808	Brick in mortar, foundation and basement ...	"	
4	1,443	Brick in mud superstructure	"	
5	25	Burnt stone slabs 6" (lintel)	S. ft.	
6	55	Burnt stone slab nicely dressed (6")	"	
7	108	Stone pillar with 3 holes for fixing bamboos in stalls, dressed	"	
8	102·23	Teak wood wrought and put up	C. ft.	
9	13·74	Roofing with 1st class Mangalore tiles on reepers ...	Sqr.	
10	81	Ridge tiles set in mortar	R. ft.	
11	144	Zinc sheet for valley	S. ft.	
12	70	Teak wood door with zinc sheet shutters, trellis, etc., as per design	"	
13	35	Teak wood windows battenned iron bars and iron fittings	"	
14	12	Teak wood ventilators with glazed shutters and iron bars	"	
15	27·55	Plastering with mortar	Sqr.	
16	27·55	White washing	"	
17	L. S.	Wood oiling	L. S.	
18	2·20	Flooring with Cuddapah slab	Sqr.	
19	240	Floor with burnt stone slab	S. ft.	
20	4·00	Gravelling and smoothening	Sqr.	
21	24	Drain with cement plaster	R. ft.	
22	163	Ordinary eave board	"	
23	7	Teak wood double pillar with capital	Each	
24	L. S.	Levelling ground	L. S.	
25	3	Teak wood finials	Each	

Statement of the probable quantities for constructing a Kitchen Block to Mr. Chamappaji Urs' Bungalow.

No.	Quantity	Details of work	Per	Remarks
1	84	Earth work excavation for foundation	C. yd.	
2	441	Concrete with mortar	C. ft.	
3	2614	Burnt brick in mortar foundation and basement ...	,,	
4	5187	Burnt brick in mortar superstructure	,,	
5	159	,, stone slabs (4½"-6") 2 lines dressed over basement and steps	S. ft.	
6	751	Burnt stone slabs (4½") dressed over lintels, etc. ...	,,	
7	392	Teak wood doors panelled with iron fitting complete	,,	
8	327	Teak wood windows with iron bars outerpanel shutters (1½" thick) and iron fittings complete ...	,,	
9	189	Teak wood iron ventilators with iron bars, outer glass shutters (1½" thick) with iron fittings ...	,,	
10	12	Raw stone pillars 9"x9" 7½' height and bases and capitals dressed	each	
11	226·73	Teak wood wrought and put up	C. ft.	
12	75·25	Rolled steel beams and joists	Cwt.	
13	15·05	Jack arched terrace	Sqr.	
14	28·98	Roofing with 1st class Mangalore tiles and teak reepers	,,	
15	168	Ridge tiles set in mortar	R. ft.	
16	324	Plain teak eave board (9")	,,	
17	109·12	Plastering with mortar	Sqr.	
18	109·12	White washing 2 coats	,,	
19	30·09	Colour washing	,,	
20	108	Parapet wall (1½') ordinary	R. ft.	
21	L. S.	Chocolate painting	L. S.	
22	,,	Wood oiling to wood work	,,	
23	189	Earth filling basement watering and tamping ...	C. yd.	
24	11·72	Flooring Henkey 9" sqr. tiles, 3" concrete bed and cement pointing	Sqr.	
25	1·44	Flooring burnt stone slabs (4½") 2 line dressed with 3" concrete bed and cement pointing ...	,,	
26	12·34	Flooring Cuddappah slabs with 3" concrete bed and cement pointing	,,	
27	104	Cornice heavy (9")	R. ft.	
28	2	Constructing chimneys	each	
29	90	Zinc sheet for valleys	S. ft.	
30	84	Teak wood screen	,,	

Statement of the probable quantities for constructing a Bungalow for Mr. Chamappaji Urs.

Mysore dated 10th July 1920.

S. No.	Details of work	Per.	Ground Floor Quantity	1st Floor Quantity
1	Earthwork excavation for foundation	C. yd.	206	
2	Earth filling basement watering and tamping	"	182	
3	Metal concrete in mortar	C. ft.	1381	
4	Burnt brick in mortar foundation and basement	"	5109	
5	do do superstructure	"	5166	3714
6	do do Arch work	"	155	
7	Burnt stone slabs (6") 2 lines dressed for steps etc.	S. ft.	112	
8	do (6") roughly dressed lintel etc.	"	590	254
9	Plastering with chunam	Sqr.	105·89	75·42
19	Whitewashing 2 coats	"	105·89	75·42
11	Colour-washing "	"	58·05	35·20
12	Teak-wood doors 1½" panel shutters with iron fittings complete	S. ft.	336	334
13	Teakwood windows (1½") panel shutters outside, glazed shutters inside and iron fitting, iron bars complete	"	396	238
14	Teakwood glazed ventilator with iron fittings—do—	"	171	96
15	Teakwood circular ventilator with glazed iron fittings	"		14
16	Flooring with Cuddapah slabs with 3" concrete bed cement pointing	Sqr	17·96	
17	Flooring 9"x9" Henkey's tiles with mortar bed and cement pointing	"		19·16
18	Roofing with jack arched terrace	"	22·38	
19	Teakwood wrought and put up	C. ft.		291·67
20	Rolled steel beams and joists	Cwt.	94·03	
21	Raw stone pillars (9"x9") 9' with capitals and bases	each	8	
22	Silicate painting 3 coats	Sqr.	21·28	15·47
23	Cornice 9" thick	R. Ft.	260	202
24	Parapet wall masonry 2½' high	"	52	
25	Mortar bedding and panel work	L. S.		
26	Roofing with 1st class Mangalore tiles and teak reepers	Sqr.		26·53
27	Bengal terrace roof	"		2·70
28	Ornamental ridge tiles, set in mortar	R. ft.		79
29	Teakwood sunshades complete with paint	No.		1
30	Teakwood ornamental eave board 9" with paint	R. ft.		161
31	Teakwood ornamental railings do	"		75
32	Chunam border	"		66
33	Masonry finials	No.		3
34	Clearing site and levelling ground	L. S.		

H. F. MARKER,
Executive Engineer,
Palace Maramath Department.

MISCELLANEOUS DEPARTMENTS.

GOVERNMENT GARDENS.

Notice.

Notice is hereby given that separate tenders for articles shown in Lists A. B. C. D. E F. G. and H. appended herein will be received uptill end of this month by the Superintendent, Government Gardens, Bangalore, for the supply by contract, of food stuffs for the Lal-Bagh Zoo and Tools; Plant, etc., for the Gardens, from 1st August 1920 to 30th June 1921 both days inclusive.

2. No tender will be received after the date mentioned above.

3. Tenders to be superscribed "Tender for the supply of food stuffs, etc., to Government Gardens.

4. No tender will be received unless submitted with a deposit of Rs. 100 in cash or currency notes except in the case of tenders for articles in list F. (Pots) and G. (Bamboo baskets) and H. Ropes, which requires a deposit of Rs. 20.

5. Tenders will be opened on the afternoon of 29th July 1920 at the office in Lal-Bagh.

6. Any tender may be rejected without reasons being assigned therefor.